

SKA EWG

# VLBI & AIV

国立天文台 河野裕介






# CONTENTS


- EWG
  - CSP (Central Signal Processor)
    - VLBI
  - AIV (Assembly, Integration, and Verification )

# CENTRAL SIGNAL PROCESSOR





- 4つのビーム
- Lead: NRC(Canada)
- コスト€80M




# VLBI CSP

- No common sky
  - Complementary network to EAVN
- Contribute VLBI components to SKA1
  - Currently available component
    - Digital Signal Processing and Recording



# VLBI BEAM FORMING

- Four beams
  - CBF produce cross corr. data for calib.
- DBBC
  - Tunable 10kHz
  - BW: 1, 4, 16, 32, 64, 128, 256, 512 MHz
- Adder 4 x 8 x 8
- Total 320 Gbps/4beams



REQ-358	Upon command from CSP_Mid.LMC, CSP_Mid.CBF shall re-configure the centre frequency, frequency band, and/or bandwidth for each tied-array VLBI beam, in less than 20 seconds (TBC).
---------	--

モード変更20秒以内

REQ-1647	CSP_Mid.CBF shall send tied-array beam data to pulsar search and timing, and VLBI outputs, with a maximum latency of 0.1 seconds (TBC).
----------	---

バッファサイズ0.1秒以上

# REQUIREMENTS

REQ-352	CSP_Mid.CBF shall be able to generate data from the VLBI beams with samples traceable to a timestamp with an accuracy of 1 nsec or better.
---------	--

未知のタイムスタンプのずれ1n秒

REQ-350	The CSP_Mid CBF shall be a data source for VLBI data acquisition system. The interface between the CSP_Mid CBF and the external VLBI data acquisition system shall be compliant with the ICD SKA-TEL-SKO-0000116.
---------	---

VLBIのIF

REQ-640	CBF components shall be capable of surviving pressures down to 11 kPa (equivalent altitude ~50,000 feet) during transport.
---------	--

真空対応

REQ-353	CSP_Mid.CBF shall be able to output VLBI beams with a sampling rate selectable between Nyquist and at least factor 2 oversampled rates for the selected bandwidth.
---------	--

オーバーサンプリング

REQ-652	CBF shall be fully operational and available 0.9991 (TBC) or more of the time.
---------	--

運用時間率

Req ID	Req Text
REQ-157	CBF shall operate as specified in these requirements for at least 20 years after acceptance.

20年保証

# KEY REQUIREMENTS

- Some prototyping needed
- 2018

REQ-366	Within the bandwidth claimed to be spectrally pure, CSP_Mid.CBF shall induce no spectral distortion in the VLBI data above -40dB TBC in amplitude and $1e-2$ radians TBC in phase after calibration.
---------	--

REQ-349	When performing VLBI beamforming, the CSP_Mid.CBF shall achieve a Signal to Noise ratio better than 98% compared to an ideal analogue beamformer, given the same digitized inputs and calibration.	No	Section 6.1. Not easily possible due to bandwidth expansion. Can achieve 97%.
---------	--	----	---



# 計画

- 2018
  - プロトタイプ
    - ソフトウェアシミュレーション
    - ハードウェア構成見積もり
    - OCTADISK2の40GE化
- 2019
  - プロトタイプ評価
  - PDR
- 2020～
  - CDR
  - インストール


# JUMPING JIVE PROJECT




- EUのプロジェクト
  - 4年/3M euro
  - 8か国
- Global VLBIとSKAとのIFを目的としている
  - SKAのCSPを分担するとは書いていない
- February 21 marks the official start of the project with a kick-off meeting in Leiden

# SKA2への展望

- SKA2ではCSPコアを狙う
  - 演算  $\propto N^2$
- ムーアの法則の限界
  - 分散処理
- SKA1CSP ではFIREFLY
  - 1.5W/28Gpbs=50mW/G
  - Passive Opt. Switch



SKA2では超低消費電力の光IOコア (PETRA) 5mW/Gbps



冷却水10°C




# 液没計算機

- 東工大 TSUBAME-KFC
  - スパコンの電力効率ランキング  
Green500, Green Graph 500の  
両方において世界一位
  - PUE=1.15



自然大気



# 実績

CPU Base (NiCT/NAOJ)  
Oyama et al, 2012  
Oyama et al, 2016



FPGA base(KASI/NAOJ)  
Oh et al, 2011



気球気密計算機 熱制御

HPC (NAOJ)

# CSP VLBIまとめ

- まずはVLBIバックエンドでSKA1に参入する
  - これまでのVLBIの技術開発の延長
    - NAOJ, CRL/NICT, ISAS, UNIVs
- SKA2で天文学史上最高集光力の集光部分(CSP)を狙う
  - グリーンコンピューティング

# ASSEMBLY, INTEGRATION & VERIFICATION



- Assembly, Integration & Verification
  - Lead: SKA SA
  - €20M
- タスク
  - ロールアウト計画立案
  - Detailed Integration and Verification Planを作成
- 納品検査の後、フルオペのサイエンスコミッションの前



# I&V Plan for SKA-LOW

## Flow Chart (Example)


ASSEMBLY, INTEGRATION, VERIFICATION

- Station roll out

- Station level tests
- Station correlation tests
- Weather condition tests
- Station calibration tests
- RFI mitigation tests
- Clock accuracy tests

- Array roll out

- 4 stations → 20 → Core → Core+3 arms



# CLARIFICATION OF ROLES AND RESPONSIBILITIES

- AIVだけが作業を行うのではない
  - どのメンバが必要かを検討
  - スケジュール・FTEを検討

		Subsystem team	Engineering Support team	SE team	Commissioning team	Operators	Maintenance team
Subsystems	Lab integration	execute	-	-	-	-	-
	Qualification testing	execute	-	observe	-	-	-
	Qualification review (QR)	execute	-	participate	participate	-	-
	Install on site	execute	-	-	-	-	-
	Site acceptance test	execute	-	observe	-	-	-
System	Lab Integration & fixing problems	support	execute	coordinate & execute	-	-	-
	Lab testing	support	support	execute	-	-	-
	Site integration and fixing problems	support	execute	coordinate & execute	-	-	support
	Acceptance testing	-	support	execute	support	-	support
	Acceptance Review	-	-	execute	participate	-	-
	Commissioning	-	support	-	execute	support	support
	Operation	-	-	-	-	execute	support
	Maintenance	-	support	-	-	-	execute

# VERIFICATION EVENT

			FTE Days
AA1 MID - Time and Frequency Reference		Non precision Time Stamping Accuracy	10
	Time Stamping Accuracy		20
	Coherence Loss		5
			35

- for example,
  - タイムスタンプの精度を20FTE days
  - コヒーレンスを5FTE days
- で求めないといけない。
  - どういう手法なのかは、資料にない。WPCに入れば見れる？

# なぜAIVか

- Understaffed

## AIV Consortium

- Achievements
  - Verification Requirements document is under Office review
  - Product Handover Checklist document is under Office review
  - Successful AIV workshops at Eng. Meeting
- Ongoing
  - Preparation of documentation pack for System Pre-CDR
  - Integration & Verification Plans for Mid and Low
  - Roll-Out Plans stable, minor refinements in version 6 expected
- Issues
  - AIV Consortium remains understaffed with no view on improvements
- AIV Consortium funding approved until end of 2018

# ALMA AIV



## Report on ALMA AIV

Lewis B.G. Knee  
AIV Test Scientist

November 2008



This report is intended to inform the Canadian ALMA Science Advisory Committee on activities within the Assembly-Integration-Verification (AIV) group at ALMA in Chile.



Report on ALMA AIV, Knee 2008

# 月面裏側 低周波電波望遠鏡

- 必要分解能0.1 deg@3MHz
  - Baseline 60km程度
- Daedalus crater Lunar Far Side
  - 直径80km



# AIV Stage 2 Milestonesスケジュール

ASSEMBLY INTEGRATION & VERIFICATION

#	Stage 2: Milestone Description	Due Date
1	Kick-off	Apr 2015
2	Telescope Preliminary I&V Plan	Jul 2015
3	SEMP and PMP Alignment	Jun 2015
4	Product Hand-Over Checklist	Jul 2015
5	Updated Cost Model	Aug 2015
6	MeerKAT Precursor ICDs	Aug 2015
7	Telescope Roll-Out Plan (Next Release)	Sep 2015
8	MeerKAT Precursor Integration Plan and ICDs	Oct 2016
9	Telescope Verification Requirements (Next Release)	Mar 2017
10	Product Hand-Over Checklist	Apr 2017
11	Telescope Detailed I&V Plan	May 2017
12	Telescope AIV Resource Plan	May 2017
13	Telescope Test Procedures (Draft)	Aug 2017
14	System Pre-CDR - Document Submission	Aug 2017
15	System Pre-CDR - Closure	Oct 2017
16	Telescope Test Procedures (Final)	Dec 2017
17	System CDR - Document Submission	Mar 2018
18	System CDR - Closure	System CDR + 4 weeks

ここまで終了  
by SKA board 2017 の  
Engineering Report



# AIV TEAM



*Figure 1: AIV Team at the Engineering Meeting in Rotterdam, June 2017. Adam MacLeod, Richard Lord, Peter Hekman, Donald Gammon, Michael Hayes, Nico Ebbendorf, Marchel Gerbers*



# AIVまとめ

- AIV
  - 計画と評価設計などの人的貢献が中心
  - LOWでの参加がいいのでは？
    - LOWにも日本が正式参加
    - 20MEなので少額でコスト貢献インパクト大きい